KOLAR DIVISION.

Dated 9th May 1904.

The attention of the public is invited to the Notification in the Gazette No. 20, dated 19th May 1904, calling for tenders for the work of repairing the Gajjanpalli tank, Registered No. 187 of Mulbagal Taluk.

Dated 9th May 1904.

The attention of the public is invited to the notification in the Gazette No. 20, dated 19th May 1904, calling for tenders for the work of restoring Tirumani tank, Registered No. 42 of Gudibanda Sub-Taluk.

B. SUBBA RAO, *Executive Engineer.*

CHITALDRUG DIVISION.

The 29th May 1904.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 20th June 1904, for constructing the Memorial Hall at Davangere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing the Memorial Hall at Davangere" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of the probable quantities of constructing Chamaraja Memorial Hall at Davangere, Chitaldrug District.

Items of work.	*Per.*	*Quantity.*
Earthwork excavation	C. yd.	90
Earth filling basement	"	98
Stone in mortar	C. ft.	4,131
Brick in mortar	"	5,423
Do arch work	"	509
Stone slabs, roughly dressed	S. ft.	986
Plastering with chunam	Sqr.	94·51
Pointing do	"	5·64
Flooring with Mangalore squire tiles over 3" concrete and cement pointing, complete.	Sqr.	17·53
Roofing with 1st class Mangalore tiles with teak reepers, etc., complete	"	15·34
Ridge tiles set in mortar	R. ft.	48
Terrace pakka 9" thick	Sqr.	10·87
Teakwood work including wood oiling	C. ft.	245·11
Iron trusses 11¼ ft. apart, complete, including the tie rod, King-posts, struts and principal rafters with railway fare from Bombay to Davangere with fixing charges, etc., etc.	Each	3
White-washing 2 coats	Sqr.	73·54
Colour-washing	"	13·63
Teakwood doors pannelled with brass hinges, bolts, etc., complete	S ft.	372
Teakwood windows, pannelled shutters, iron bars, etc., complete	"	283
Teak wood ventilators with iron bars and glazed shutters, etc., complete	S. ft.	128
Circular ventilators with glazed shutters	"	6
Plain cornice (thin and thick)	R. ft.	422
Ordinary parapet wall with pedestals	"	156
Finials (large)	Each.	2
Do (small)	"	22
Wooden ladders for upstair verandah rooms	"	1
Chocolate painting to doors, windows and ventilators, etc.,	Sqr.	12·00
Levelling ground (earth to be brought from near goods shed).	C. yd.	990
Side drains for roads	"	111

Y. SRINIVASA RAO, *Executive Engineer.*